

DBIÓR ZABEZPIECZEN		OBCIĄŻENIE					KABEL, PRZEWÓD								ZABEZPIECZENIE				WYNIK			
LP	odbiór	P _i (kW)	k _j	cosφ	P _o (kW)	I _b (A)	Typ	s (mm)	I _{dd} (A)	k _g	I _z (A)	l (m)	ro	delta U (%)	I _n (A)	k _z zab.	I ₂ (A)	1,45xI _z	I _b < I _n < I _z	I ₂ < 1,45I _z	delta U	zabezp. I _n
1	2	4	5	6	7	8	9	10	11	12	13	14	15	16	17	19	20	21	22	23	24	25
1	3 fazowy (400V)	5,8	1,00	0,93	5,8	9,0	YKY 5x4	4	31,0	1,00	31,0	75,0	57	1,2	16,0	1,6	25,6	45,0	OK	OK	OK	OK